



Public Informational Material

Project I.D. 9877-03-01/71

T Pelican, Haymeadow Road

Haymeadow Creek Bridge P-43-0058

Oneida County



Building a Better World
for All of Us®

Engineers | Architects | Planners | Scientists

Public Informational Material

Haymeadow Road

Prepared for the Town of Pelican

1 Project Description

The proposed project involves the removal and replacement of the existing structure on Haymeadow Road over Haymeadow Creek in the Town of Pelican, Oneida County. **See Haymeadow Rd Project Location Map.** The existing structure has reached the end of its useful life expectancy. The existing structure (P-43-0058) consists of a 34-foot single-span concrete girder, a traveled way width consisting of two 10-foot driving lanes, and no defined shoulders. The existing structure was built in 1917 and has undergone routine inspection and minor maintenance.

The proposed undertaking consists of the construction of a single-span reinforced concrete flat slab bridge (B-43-0070) with approximately 250 feet of approaches. The traveled way and shoulder widths will receive 20-feet of new asphaltic pavement and 3-foot gravel shoulders. **See Haymeadow Rd Preliminary Plan Sheets.**

The speed limit of the project limits is 45 mph, posted. Right-of-way acquisition is expected in the form of Temporary Limited Easements.

2 Reason for Project

- Substructure in serious condition
- Structural deficiencies
- Roadside Safety and Maintenance

3 Traffic Volumes

- 72 Vehicles per day (2026)
- 78 Vehicles per day (2046, design year)
- 10% trucks

4 Proposed Roadway Details

- Using Existing Alignment
- Reconstruction of roadway approaches (250 feet total)
- New Asphalt Pavement
- New Gravel Shoulders

5 Proposed Structure Details

- Superstructure Type: Single-Span Reinforced Concrete Flat Slab Bridge
- Railing Type: 42SS Single Slope Concrete Parapet
- Clear Width: 24 feet
- Structure Length: 50.58 feet
- Skew: 15° Left-Hand Forward
- Wingwall Formation: 45° Wings

6 Traffic During Construction

- Roadway will be Closed to Traffic
 - No detour provided in plan.

7 Scheduling Dates

- Final Plan, Specifications & Estimate: August 1, 2025
- Letting Date: January 13, 2026
- Begin Construction: 2026

8 Contacts

- | | |
|--|------------------------------|
| • <u>Design Consultant</u> | <u>Town</u> |
| Project Manager: Chris Blum, P.E. (WI) | Town Chairman: Nick Scholtes |
| Short Elliott Hendrickson, Inc. | 4694 Old 8 Road |
| 6808 Odana Road, Suite 200 | Rhineland, WI 54501 |
| Madison, WI 53719 | 715-401-3755 |
| 608-620-6192 | pelicanchair1@gmail.com |
| cblum@sehinc.com | |

Building a Better World for All of Us[®]

Sustainable buildings, sound infrastructure, safe transportation systems, clean water, renewable energy and a balanced environment. Building a Better World for All of Us communicates a company-wide commitment to act in the best interests of our clients and the world around us.

We're confident in our ability to balance these requirements.

[Join Our Social Communities](#)

